FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-6K-I	ST. CLAIR	188	77
STA. _____		TO STA. _____		
CONTRACT NO.: ~~76796~~ 76815				

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCHEDULE OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE Y031-1F HARTMAN LANE	NW/SW I-64 RAMPS	NE/SE I-64 RAMPS	LIGHTING
72000100	SIGN PANEL - TYPE 1	SQ FT	20	12.5		7.5	
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	5	5			
80300100	LOCATING UNDERGROUND CABLE	FOOT	5000	725	725	725	2825
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	301	56	122	123	
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1167	144	963	60	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	103		14	32	57
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	17		17		
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	39		39		
81018400	CONDUIT PUSHED, 1 1/2" DIA., GALVANIZED STEEL	FOOT	111		59	52	
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	87		87		
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	105		105		
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	90		90		
81400400	CONCRETE HANDHOLE	EACH	8	2	5	1	
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1		1		
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4452	200	1155	215	2882
81500205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	52	10	18	24	
81600115	UNIT DUCT, 2*10XLP,1*10 XLP GROUND 3/4" POLYETHYLENE	FOOT	119				119
81600515	UNIT DUCT, 2*2XLP,1*2 XLP GROUND 1 1/4" POLYETHYLENE	FOOT	2707				2707
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	28				28
84200700	LIGHTING FOUNDATION REMOVAL	EACH	4				4
87300305	ELECTRIC CABLE IN TRENCH, LEAD-IN, NO. 14 1 PAIR	FOOT	11115	1675	6315	3125	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2980		1799	1181	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	348		348		
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	7		4	3	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	21		12	9	
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	15		15		
87900200	DRILL EXISTING HANDHOLE	EACH	10	2	7	7	
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	5		4	1	
88500100	INDUCTIVE LOOP DETECTOR	EACH	8	3	4	1	
88600100	DETECTOR LOOP, TYPE I	FOOT	5341	852	2382	2107	

Rev.

PLOT DATE: 7/1/2005

$$DATE$$
7/1/2005
c:\pw_work\ed0694\electrical\tsp\d6984x.dgn
$$REF-
$$REF-
$$REF-