F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
360	03-00320-00-TL	KANE	33	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83808

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: Y031-1F

	CODE NO.	PAY ITEM	UNIT	(1) Kirk Rd @ Pine St	(2) Kirk Rd @ Wilson St	(3) Kirk Rd @ Hubbard Ave	(4) Kirk Rd @ Fabyan Pkwy	(5) Kirk Rd @ Cherry Ln	(6) Kirk Rd @ IL Rte 38	(7) Kirk Rd @ Division St	(8) Kirk Rd @ Tyler St	(9) Kirk Rd @ Ohio Ave/DuKane Dr	(10) Interconnect	TOTAL
*	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM										1	1
	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	513			12	218					25138	25881
	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT				5							5
	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT					40					1119	1159
	81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT										1392	1392
	81300810	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 8"	EACH										4	4
	81400100	HANDHOLE	EACH	2				1					43	46
	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	513			17	218					25138	25886
	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	1	1	1	1	1	1	1		9
*	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH		1	1								2
*	85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH				1							1
*	85700505	FULL-ACTUATED CONTROLLER IN EXISTING CABINET, SPECIAL	EACH					1	1	1	1			4
	86400100	TRANSCEIVER - FIBER OPTIC	EACH		1	1	1	1		1	1	1		7
	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT										31502	31502
*	XX003660	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125 MM24F & SM12F	FOOT										31692	31692
	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT		255		94	87	81	80	221			818
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	827		799	714	1590		806		780		5516
	XX003583	VIDEO ELECTRIC CABLE IN CONDUIT, NO. 16 3C	FOOT		255		94	87	81	80	221			818
	XX003584	VIDEO BELDEN 8281 COAXIAL CABLE IN CONDUIT	FOOT		255		94	87	81	80	221			818
	87800200	CONCRETE FOUNDATION, TYPE D	FOOT				4							4
	87900200	DRILL EXISTING HANDHOLE	EACH	2	2	2	4	7	2	2	2	2	1	26
	88500100	INDUCTIVE LOOP DETECTOR	EACH	2	8	9	10	4		2		2		37
	88600100	DETECTOR LOOP, TYPE I	FOOT					66						66
*	89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH		1		1							2
*	89502200	MODIFY EXISTING CONTROLLER	EACH	1								1	1	3
	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH		1	1	1	1	1	1	1			7
*	X8780110	MODIFY EXISTING TYPE "D" FOUNDATION	EACH		1	1	1							3
	X8950100	RELOCATE EXISTING MASTER CONTROLLER	EACH										1	1
*	XX002856	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM	LSUM										1	1
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM										1	1
*	XX005940	REMOTE-CONTROLLED VIDEO SYSTEM	EACH		1		1	1	1	1	1			6
*	XX006390	VIDEO COMMUNICATIONS SYSTEM AND CABINET	EACH				1							1
	XX005462	CHANGEABLE MESSAGE SIGN	WEEK		2	2	2							6
△	Z0076600	TRAINEES	HOUR										500	500
	67100100	MOBILIZATION	LSUM										1	1

* SEE SPECIAL PROVISIONS

△ Y080

KENIG, LINDGREN, O'HARA, ABOONA, INC.
9575 West Higgins Road, Suite 400
Rosemont, Illinois 60018
(847) 518-9990 FAX (847) 518-9987

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

KIRK RD.
FROM PINE ST. TO IL RTE 64

SCALE: NONE

DATE: 07/19/05

DRAWN BY: DMS
DESIGNED BY: DMS
CHECKED BY: DMS