F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
	03-P4045-01-BT	COOK	080	004
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83811

SUMMARY OF QUANTITIES

Y052

S.I.	CODE NO.	PAY ITEM	UNIT	QUAN
	20200100	EARTH EXCAVATION	CU YD	11320
	20100500	TREE REMOVAL, ACRES	ACRE	3
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	200
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	49000
*	25000200	SEEDING, CLASS 2	ACRE	10.1
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	910
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	910
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	910
*	25100630	EROSION CONTROL BLANKET	SQ YD	49000
	28000400	PERIMETER EROSION BARRIER	FOOT	24200
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	16150
	35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	12
	40500100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8075
	42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	15
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	800
	44003100	MEDIAN REMOVAL	SQ FT	275
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	110
	60611600	COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	FOOT	160
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	110
	67100100	MOBILIZATION	L SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
*	72000100	SIGN PANEL - TYPE 1	SQ FT	120
*	73000100	WOOD SIGN SUPPORT	FOOT	204
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	670
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	6
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
*	81000400	CONDUIT IN TRENCH, 1 1/4" DIA., GALVANIZED STEEL	FOOT	2400
*	81018300	CONDUIT PUSHED, 1 1/4" DIA., GALVANIZED STEEL	FOOT	500
*	81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	144
*	85800100	FLASHER CONTROLLER	EACH	6
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3044
*	D2003724	EVERGREEN, THUJA OCCIDENTALIS (AMERICAN ARBORVITAE), 2' HEIGHT, BALLED AND BURLAPPED	EACH	620
*	X0323319	POST MOUNTED FLASHING BEACON INSTALLATION (SPECIAL)	EACH	12
*	X0324056	REMOVAL OF EXISTING WOOD BOLLARDS	EACH	3
*	X0350805	FOLD DOWN BOLLARDS	EACH	13
	X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	1860
	Z0064600	SELECTIVE CLEARING	ACRE	3
Δ	Z0076600	TRAINEES	HOUR	500
	42400800	DETECTABLE WARNINGS	SQ FT	256

Δ = Y080

* - INDICATES SPECIALTY ITEMS

ROBINSON ENGINEERING, LTD.
CONSULTING REGISTERED PROFESSIONAL ENGINEERS AND PROFESSIONAL LAND SURVEYORS
17000 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473
(708) 331-6700 FAX (708) 331-3629

© COPYRIGHT 2005

ILLINOIS DESIGN FIRM REGISTRATION NO. 184001128.

SUMMARY OF QUANTITIES
PENNSY GREENWAY BIKE PATH

LANSING, ILLINOIS

Drawn by:	LTL	Date:	7/22/05
Checked by:	JP	Scale:	N/A
Sheet	004 of 080	Project No.	03-365.02

REVISIONS		
No.	Date	Remarks

03365-QUAN-01 - DTLS01