

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			12	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

•VARIOUS
 ••D9 CONT MAINT FY 06-1
 •••VARIOUS

PAVEMENT SCHEDULE

STATION (LOCATION)	PCC PAVEMENT 10"	SUBBASE GRAN MATL TY A 4"	PCC INLAY 3"	PAVT. REMOV. SPECIAL	PAVEMENT REMOVAL	SAW CUTS	PAVEMENT FABRIC	PROTECTIVE COAT	CORR MEDIAN REMOVAL	CONC MED SURF REM	COMB CURB & GUT REMOV	COMB CC&G TY M-6.06
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	SQ YD	SQ FT	SQ FT	FOOT	FOOT
LOCATION 1												
ILL 142 (EQUALITY)												
315+66.84 - 316+17	18	18					18	18	160			
315+66.84 - 315+77										20	25	25
Rt. 315+66.84 - Rt. 316+85	223	243			223		223	223				
Lt. 315+66.84 - Lt. 316+85	204	224			204		204	204				
LOCATION 3												
ILL 13/US 45 (HARRISBURG)												
Lt. 1076+09 (IL 13)			10.0	10.0		87						
1075+65 (IL 13)			27.0	27.0		198						
Lt. 29+60 (US 45)			8.0	8.0		66						
LOCATION 2												
ILL 146/MAIN ST. (ANNA)												
Rt. 128+88			10.0	10.0		81						
Lt. 1073+10			11.0	11.0		97						
Lt. 1074+12			12.0	12.0		93						
Rt. 1074+50			30.0	30.0		213						
TOTAL	445	485	108	108	427	835	445	445	160	20	25	25

PAVEMENT MARKING SCHEDULE

STATION TO STATION	POLYUREA PAVEMENT MARKING			NOTES
	LINE - 24 INCH	LINE - 4 INCH		
	SOLID YELLOW FT	SOLID WHITE FT	SOLID YELLOW FT	
ILL 142 (EQUALITY)				
Lt. 315+66 - 316+85		119	238	Edge lines
Rt. 315+66 - 316+85		119		Edge lines
Lt. & Rt. 315+66 - 316+85			25	Top of Curb
ILL 13/US 45 (HARRISBURG)				
Lt. 1076+09 (IL 13)	12			Stop Bar
Sub-Totals	12	238	263	
TOTAL	12	501		

PLOT DATE = 7/7/2005
 FILE NAME = c:\p\projects\982785\p82785.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = recorder